

**FIRE ALARM CABLE SCHEDULE – FLOTATION**

ITEM	REV	CABLE ID	FUNCTION	CABLE SIZE	CABLE TYPE	INSULATION	LENGTH (FT) *** NOTE 1	SOURCE AREA	SOURCE EQUIPMENT	DESTINATION AREA	DESTINATION EQUIPMENT	DRAWING REFERENCE / NOTES
1		POWER PANEL/FCP02	POWER	2C/#14	TECK 90	600V, 90 DEG C XLPE	50	FLOTATION E-HOUSE	POWER PANEL	FLOTATION E-HOUSE	FCP02	
2		FIBER PANEL/FCP02	FIBER	PATCH CABLE SM DUPLEX ST-LC	CONDUIT OR FLEX	N/A	50	FLOTATION E-HOUSE	FIBER PANEL	FLOTATION E-HOUSE	FCP02	QTY 2 REQUIRED FOR DATA IN AND DATA OUT.
3		FL-FJB01/L1-D-01	LOOP #1	2C/#14	TECK 90 RED	600V, 90 DEG C XLPE	20	FLOTATION E-HOUSE	FL-FJB01	FLOTATION E-HOUSE WEST DOOR	L1-D-01	NBD-9109 120
4		L1-D-01/L1-D-02	LOOP #1	2C/#14	TECK 90 RED	600V, 90 DEG C XLPE	30	FLOTATION E-HOUSE WEST DOOR	L1-D-01	FLOTATION E-HOUSE SOUTH	L1-D-02	NBD-9109 120
5		L1-D-02/L1-D-03	LOOP #1	2C/#14	TECK 90 RED	600V, 90 DEG C XLPE	30	FLOTATION E-HOUSE SOUTH	L1-D-02	FLOTATION E-HOUSE NORTH	L1-D-03	NBD-9109 120
6		L1-D-03/L1-M-04	LOOP #1	2C/#14	TECK 90 RED	600V, 90 DEG C XLPE	20	FLOTATION E-HOUSE NORTH	L1-D-03	FLOTATION E-HOUSE EAST DOOR	L1-M-04	NBD-9109 120
7		L1-M-04/L1-M-05	LOOP #1	2C/#14	TECK 90 RED	600V, 90 DEG C XLPE	20	FLOTATION E-HOUSE EAST DOOR	L1-M-04	FLOTATION E-HOUSE	L1-M-05	NBD-9109 120
8		FL-FJB01/L1-D-06	LOOP #1	2C/#14	TECK 90 RED	600V, 90 DEG C XLPE	20	FLOTATION E-HOUSE	FL-FJB01	COMPRESSOR HOUSE #2	L1-D-06	NBD-9109 120 AND NBD-9109 123 TO BE VERIFIED BY SUPPLIER
9		L1-D-06/L1-D-07	LOOP #1	2C/#14	TECK 90 RED	600V, 90 DEG C XLPE	20	COMPRESSOR HOUSE #2	L1-D-06	COMPRESSOR HOUSE #2	L1-D-07	NBD-9109 123 TO BE VERIFIED BY SUPPLIER
10		L1-D-07/L1-M-08	LOOP #1	2C/#14	TECK 90 RED	600V, 90 DEG C XLPE	20	COMPRESSOR HOUSE #2	L1-D-07	COMPRESSOR HOUSE #2	L1-M-08	NBD-9109 123 TO BE VERIFIED BY SUPPLIER
11		L1-M-08/L1-M-09	LOOP #1	2C/#14	TECK 90 RED	600V, 90 DEG C XLPE	20	COMPRESSOR HOUSE #2	L1-M-08	COMPRESSOR HOUSE #2	L1-M-09	NBD-9109 123 TO BE VERIFIED BY SUPPLIER
12		L1-M-09/L1-IM-10	LOOP #1	2C/#14	TECK 90 RED	600V, 90 DEG C XLPE	20	COMPRESSOR HOUSE #2	L1-M-09	COMPRESSOR HOUSE #2	L1-IM-10	NBD-9109 123 TO BE VERIFIED BY SUPPLIER
13		FL-FJB01/L1-IM-11	LOOP #1	4C/#14	TECK 90 RED	600V, 90 DEG C XLPE	150	FLOTATION BUILDING MAIN FL - PROCESS RM EAST WALL	FL-FJB01	FLOTATION BUILDING MAIN FL - PROCESS RM EAST WALL	L1-IM-11	NBD-9109 120 AND NBD-9109 121
14		L1-IM-11/L1-D-12	LOOP #1	2C/#14	TECK 90 RED	600V, 90 DEG C XLPE	40	FLOTATION BUILDING MAIN FL - PROCESS RM EAST WALL	L1-IM-11	FLOTATION BUILDING MAIN FL - PROCESS RM SE CORNER DOOR	L1-D-12	NBD-9109 121
15		L1-D-12/L1-M-13	LOOP #1	2C/#14	TECK 90 RED	600V, 90 DEG C XLPE	60	FLOTATION BUILDING MAIN FL - PROCESS RM SE CORNER DOOR	L1-D-12	FLOTATION BUILDING MAIN FL - PROCESS RM SOUTH WALL	L1-M-13	NBD-9109 121
16		L1-M-13/L1-M-14	LOOP #1	2C/#14	TECK 90 RED	600V, 90 DEG C XLPE	40	FLOTATION BUILDING MAIN FL - PROCESS RM SOUTH WALL	L1-M-13	FLOTATION BUILDING MAIN FL - PROCESS RM SOUTH DOOR	L1-M-14	NBD-9109 121
17		L1-M-14/L1-M-15	LOOP #1	2C/#14	TECK 90 RED	600V, 90 DEG C XLPE	40	FLOTATION BUILDING MAIN FL - PROCESS RM SOUTH DOOR	L1-M-14	FLOTATION BUILDING MAIN FL - PROCESS RM WEST DOOR	L1-M-15	NBD-9109 121
18		L1-M-15/L1-M-16	LOOP #1	2C/#14	TECK 90 RED	600V, 90 DEG C XLPE	40	FLOTATION BUILDING MAIN FL - PROCESS RM WEST DOOR	L1-M-15	FLOTATION BUILDING MAIN FL - PROCESS RM NW CORNER	L1-M-16	NBD-9109 121
19		L1-M-16/FJB11	LOOP #1	2C/#14	TECK 90 RED	600V, 90 DEG C XLPE	40	FLOTATION BUILDING MAIN FL - PROCESS RM NW CORNER	L1-M-16	FLOTATION BUILDING MAIN FL - TRUCK BAY SW CORNER	FJB11	NBD-9109 121
20		FJB11/L1-D-17	LOOP #1	2C/#14	TECK 90 RED	600V, 90 DEG C XLPE	80	FLOTATION BUILDING MAIN FL - TRUCK BAY SW CORNER	FJB11	FLOTATION BUILDING MAIN FL - TRUCK BAY WEST DOOR	L1-D-17	NBD-9109 121
21		L1-D-17/L1-D-18	LOOP #1	2C/#14	TECK 90 RED	600V, 90 DEG C XLPE	120	FLOTATION BUILDING MAIN FL - TRUCK BAY WEST DOOR	L1-D-17	FLOTATION BUILDING MAIN FL - TRUCK BAY NE DOOR	L1-D-18	NBD-9109 121
22		L1-D-18/L1-D-19	LOOP #1	2C/#14	TECK 90 RED	600V, 90 DEG C XLPE	30	FLOTATION BUILDING MAIN FL - TRUCK BAY NE DOOR	L1-D-18	FLOTATION BUILDING MAIN FL - TRUCK BAY NE CORNER	L1-D-19	NBD-9109 121
23		L1-D-19/L1-D-20	LOOP #3	2C/#14	TECK 90 RED	600V, 90 DEG C XLPE	10	FLOTATION BUILDING MAIN FL - TRUCK BAY NE CORNER	L1-D-19	FLOTATION BUILDING MAIN FL - MAINT SHOP NE CORNER	L1-D-20	NBD-9109 121
24		L1-D-20/L1-D-21	LOOP #3	2C/#14	TECK 90 RED	600V, 90 DEG C XLPE	30	FLOTATION BUILDING MAIN FL - MAINT SHOP NE CORNER	L1-D-20	FLOTATION BUILDING MAIN FL - MAINT SHOP EAST DOOR	L1-D-21	NBD-9109 121
25		L1-D-21/L1-D-22	LOOP #3	2C/#14	TECK 90 RED	600V, 90 DEG C XLPE	30	FLOTATION BUILDING MAIN FL - MAINT SHOP EAST DOOR	L1-D-21	FLOTATION BUILDING MAIN FL - MAINT SHOP EAST WALL	L1-D-22	NBD-9109 121
26		L1-D-22/L1-D-23	LOOP #3	2C/#14	TECK 90 RED	600V, 90 DEG C XLPE	30	FLOTATION BUILDING MAIN FL - MAINT SHOP EAST WALL	L1-D-22	FLOTATION BUILDING MAIN FL - MAINT SHOP NORTH	L1-D-23	NBD-9109 121